

**CIVIL, FURNITURE AND ELECTRIC WORK (ONLY LABOUR) FOR  
RAJKOT NAGARIK SAHAKARI BANK LTD BHUJ BRANCH AT BHUJ, DIST.-KACHCHH**

**ABSTRACT**

Item No.	DESCRIPTION	Quantity	Unit	SOR - 2024/25 (Kachchh)Item Code/Page No.	SOR Rate	1% Labour Cess	Rate	Amount
<b>1</b>	<b><u>Dismantling Work</u></b>							
1.1	Dismantling doors, windows, ventilators etc. (wood or steel) shutters including chowkhats architraves, holdfasts and other attachment etc. complete and stacking them within all lead and lift. (i) Not exceeding 3 Sq.M. in area.	47.00	Nos	20013A/148	190.19	1.90	192.09	9028.00
1.2	Dismantling sanitary fittings like wash basin . W.C. pan Indian and European type, flushing tank etc. including stacking the materials with all lead and lift.	14.00	Nos	20016/148	410.13	4.10	414.23	5799.00
1.3	Dismantling of sanitary fittings like Bib-cock, pillar cock, angle cock and valves etc. including stacking the materials with all lead and lift.	33.00	Nos	MR	50.00	0.50	50.50	1667.00
1.4	Demolition of Brick work and stone masonry including stacking of serviceable materilas and disposal of unserviceable materials with all lead and lift. (ii) In Cement Mortar.	20.68	Cum	20003B/147	557.32	5.57	562.89	11641.00
1.5	Demolition including stacking of serviceable materilas and disposal of unserviceable materials with all lead and lift. (i) R.C.C. work	6.15	Cum	20002/147	1071.63	10.72	1082.35	6655.00
1.6	Dismantaling tiled of stone floors laid in mortar including stacking of serviceable materilas and disposal of unserviceable materials with all lead and lift.	121.23	Sqm	20005/147	48.63	0.49	49.12	5955.00
1.7	Removing dry or oil bound distemper by a washing and scraping and sand papering the wall and ceiling surface smooth including necessary repairs to scratches complete.	2343.42	Sqm	18014/141	11.42	0.11	11.53	27020.00
<b>2</b>	<b><u>Excavation</u></b>							
2.1	Excavation for foundation upto 1.5 m depth including sorting out and stacking of useful materials and disposing off the excavated stuff upto 50 Meter lead.(B) Dense or Hard soil	36.62	Cum	26075B/185	251.37	2.51	253.88	9297.00
2.2	Filling available excavated earth (excluding rock) in trenches. plinth, sides of foundations etc. in layers not exceeding 20 cm. in depth consolidating each disposed layer by ramming and watering.	16.00	Cum	04006/69	135.56	1.36	136.92	2191.00
<b>3</b>	<b><u>Plain Concrete Work</u></b>							
3.1	Providing and laying cement concrete 1:3:6 (1- Cement : 3-coarse sand : 6- hand broken stone aggregates 40 mm nominal size) and curing complete excluding cost of formwork in (A) Foundation and Plinth	2.85	Cum	05004A/73	2742.27	27.42	2769.69	7891.00
<b>4</b>	<b><u>Masonry Work</u></b>							
4.1	Coursed rubble masonry with stone of approved quality in foundations and plinth in Cement Mortar 1:4 (1-Cement : 4- coarse sand) etc. complete.	6.85	Cum	07005BA/92	3591.43	35.91	3627.34	24858.00
4.2	Precast concrete block masonry (including quoin blocks jamb blocks closer etc.) with solid concrete blocks of 23 cms thick approved size made of cement concrete 1:3:6 mix (1-Cement : 3 coarse sand: 6- graded stone aggregates of 20 mm and down grade) in foundation and plinth cement mortar 1:6.	22.78	Cum	07012A/93	3734.62	37.35	3771.97	85929.00
4.3	Precast concrete block masonry in partition walls 15 cm. thick with solid block of approved size (including quoin blocks Jamb blocks closer etc.) made of C.C.1:3:6 (1- Cement : 3- coarse sand : 6 graded stone aggregates 20 mm and down grade) (A) in C.M. 1:4.	47.87	Sqm	07014A/93	670.15	6.70	676.85	32402.00
<b>5</b>	<b><u>Reinforced Cement Concrete</u></b>							
5.1	Providing and laying controlled cement concrete M.250 and curing complete including the cost of formwork and <b>excluding the cost of reinforcement</b> for reinforced concrete work in (A) Foundations, footings, Base of columns and Mass concrete.	7.61	Cum	05025AA/77 + Cost of Formwork	6387.91	63.88	6451.79	49111.00
5.2	Providing and laying controlled cement concrete M.250 and curing complete including the cost of formwork and <b>excluding the cost of reinforcement</b> for reinforced concrete work in (C) Slabs,landing,shelves,Balconies, Lintels, Beams, Girders and Cantilever upto floor two level.	20.87	Cum	05024CA/77 + Cost of Formwork	7268.68	72.69	7341.37	153192.00
<b>6</b>	<b><u>Finishing</u></b>							
6.1	Providing 10mm thick cement plaster in single coat on brick/concrete walls for interior plastering upto floor two level and finished even and smooth in (ii) Cement mortar 1:4 (1-cement :4-sand)	17.19	Sqm	17001B/136	121.05	1.21	122.26	2102.00

6.2	Providing 15mm thick cement plaster in single coat on Rough (Similar)side of single or half brick walls for interior plastering upto floor two level and finished even and smooth in (ii) Cement mortar 1:4 (1-cement :4-sand)	650.42	Sqm	17002B/136	159.60	1.60	161.20	104848.00
6.3	Applying two coats of putty & two coats of primer of <b>ASIAN PAINTS</b> approved brand and manufacture on new wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth.	1481.43	Sqm	19032/146	40.19	0.40	40.59	60131.00
6.4	Interior Wall painting (two or more coats) with premium emulsion paint of <b>ASIAN PAINTS - APCOLITE</b> and manufacture on undecorated wall surface to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth.	1481.43	Sqm	18031/142	83.53	0.84	84.37	124988.00
6.5	Finishing exterior wall with weather proof exterior emulsion paint of <b>ASIAN PAINTS</b> approved brand and manufacture on wall surfaces (Two or more coats) to give an required shape, even shade and manufacture and thoroughly brushing the surface to remove all dirt and remains of loose powered materials.	861.99	Sqm	19031	119.07	1.19	120.26	103663.00
6.6	Painting two coats (excluding priming coat) on new steel and other metal surface of <b>ASIAN PAINTS</b> with enamel paint, brushing, interior to give an even shade including cleaning the surface an even shade including cleaning the surface of all dirt, dust and other foreign matter.	261.26	Sqm	19002/143	91.29	0.91	92.20	24088.00
7	<b>Flooring</b>							
7.1	Providing and laying NON SLIPPERY <b>VARMORA</b> made tiles flooring- 9 to 10mm thick , 24"x 48" on existing flooring laid on a bed of 12mm thick tile adhesive coarse finishing with flush pointing in white cement.	362.36	Sqm	MR	1516.65	15.17	1531.82	555073.00
7.2	Providing and laying NON SLIPPERY <b>VARMORA</b> made tiles 9-10mm thick , in <b>skirting</b> risers of steps and dedo on 10mm thick cement plaster 1:3 (1-cement : 3-coarse sand) and jointed with white cement slurry.	25.11	Sqm	MR	1576.63	15.77	1592.40	39990.00
7.3	Providing and laying NON SLIPPERY <b>VARMORA</b> made tiles 9-10mm thick , 24"x24" in toilet flooring treads of steps and landing laid on a bed of 12mm thick cement mortar 1:3 (1-cement : 3-coarse sand ) finishing with flush pointing in white cement.	26.16	Sqm	MR	953.58	9.54	963.12	25193.00
7.4	Providing and laying <b>VARMORA</b> made Glazed tiles 8 to 10 mm thick, 12"x24" in toilet and pantry walls and dedo on 10mm thick cement plaster 1:3 (1-cement : 3-coarse sand) and jointed with white cement slurry.	136.22	Sqm	MR	1116.32	11.16	1127.48	153590.00
7.5	Providing and laying 18 mm thick mirror polished <b>Black Granite</b> stone machine cut in single piece (Max. available) in sill and jambs laid over 10 mm thick cement mortar 1 : 3 (1 cement : 3 coarse sand) and jointed with grey cement slurry with matching pigment incl. rubbing and polishing half rounding edge both side etc. complete colour and shed as approved by architect engineer in charge. (As directed by Engineer in charge.	12.96	Sqm	14013A/128	2498.32	24.98	2523.30	32697.00
7.6	Providing and applying <b>Red sand stone</b> on the external surface of the new building walls as per the existing pattern of the stones in the building on 10mm thick cement plaster 1:3 (1-cement : 3-coarse sand) and jointed with cement slurry	109.08	Sqm	MR	2498.32	24.98	2523.30	275231.00

7.7	Providing & laying Sandwich platform of maximum 700mm width a) Sandwich type platform of top stone as 18 mm thick Granite of approved shade and sample and bottom stone as 25 mm thick single side polished kota stone with 25 mm thick screed of cement mortar 1:4 in between two stones. The stone shall be fixed by chasing in to the wall surface and providing necessary MS supports of 50x50x6mm Angle or "T" (hot dip galvanised) and embedded in between the two stones etc as per the drawing / specification and / or as instructed of EIC complete) 75 mm raised platform (Otli) at floor level with polished kota laid on 50mm screed of (1:2:4) and skirting of kota stone as per design and approved sample. The rate includes rounding, champhering and mirror polishing of edges, facias of granite, MS supports, all material labour and wastage, as per drawing, including necessary bonding adhesive (if required) of Araldite or equivalent. Rate shall be inclusive of making holes & cutouts for SS sink, Oval wash basin, Piller tap / Bib tap etc. as directed by engineer in charge. (Only finished single side granite work shall be measured & paid for).	2.57	Sqm	MR	8732.43	87.32	8819.75	22702.00
8	<b>Door / Window</b>							
8.1	Providing and fixing FRP frame size 125x65 mm and 35mm thick FRP shutter having extra reinforcement on sides & edges in polish finish. The core of the shutter & frame is to be filled up with injected polyurethane foam done in situ along with embedded wooden pieces for stiffening & also taking hinges & finiturs. The whole FRP frame & shutter is to be water proof weather proof, termite proof & resistance to mild acid/alkali. Rates are to be inclusive of S.S hinges with necessary screws & alluminium S.S fixtures & fastenings & fastener sleeve.	6.93	Rmt	10036/104	1999.98	20.00	2019.98	13998.00
8.2	Providing and fixing window having extruded aluminum Colour anodized section frame main outer size 127mm x 38.10mm x 1.35mm @ wt. 1.384kg/m, horizontal Four track member size 122.20mm x 31.75mm x 1.10mm @ wt 1.205 kg/m, vertical member of size 122.20mm x 31.75mm x 1.50mm @ 1.398 kg/mt with sliding shutters of horizontal member size 40mm x 18mm x 1.29mm @ 0.456kg/mt, vertical member of size 40mm x 18mm x 1.29mm @ 0.456 kg/mt with 5 mm thick transparent bronze colour tinted float glass with powder coated aluminum fittings and fixtures and transparent silicon sealant glass fixing to frame as per details etc complete for window.	7.18	Sqm	10026/117	2119.14	21.19	2140.33	15374.00
8.3	Providing and fixing standard extruded of alluminium section of size 63mm x 38.10mm x 1.2mm @ Wt. 0.643 Kg/mt with colour anodized alluminium frame for ventilation with 5 mm thick frosted glass as details etc complete for Ventilation	1.58	Sqm	10030/117	1163.92	11.64	1175.56	1862.00
9	<b>False Ceiling</b>							
9.1	Providing & fixing at any level/ height , solid panel type Gyproc 600x 600mm ( saint gobein) solid ceiling tiles ,This white colored, square edge, ceiling panel has a sand finish surface design on the face side along with perforations. false ceiling as per design in steps, cut-out etc, which INCLUDING perimeter channels, intermediate channels and supports, clips, cleats as per manufacturer's manual/ guidelines shall be fixed with screw with filling and finishing the tapered edges with jointing compound, paper tape. The item includes necessary frames supports from ceiling / wall at cut out for light fitting, AC grills, diffusers and cut outs i/c cutting of opening for light fixtures etc. All complete as per design. etc. complete as per direction of architect / engineer in charge. shall be done as per requirement at site. Note-1 : for measurement purpose : only room plane area should be measured no steps will be count differently .	227.70	Sqm	10060/113	1600.00	16.00	1616.00	367963.00
9.2	Providing and fixing single layer gypsum board 12.5 mm thick sections using board of size 1220 mm x 1830 mm x 12.5 mm suspended by GI suspender channel of size 25 mm x 3 mm with intermediate channel of size 18 mm x 40 mm x 0.8 mm at 1220 mm center to center ceiling section of size 40 mm x 35 mm x 0.55 mm at 457 mm c/c and perimeter channel A of size 20 mm x 27 mm x 30 mm x 0.5 mm at edges & drops including paper tap sand sofit cleat, anchor fastener, scotch bolt connecting cleat, joining compound top coat on ceiling incl. making necy. opening for light fitting, diffuser etc. comp. as per detail drawing as directed.	143.00	sq.mt	MR	704.00	7.04	711.04	101679.00
10	<b>STEEL REINFORCEMENT</b>							

10.1	Providing <b>TMT Bar FE 500D reinforcement</b> for R.C.C. work including bending, binding and placing in position complete upto floor two levels.	2436.72	Kg	05014C/75	76.52	0.77	77.29	188334.00
10.2	Providing and fixing mild steel dowel bars (For Rebaring) of minimum 12mm dia. for anchoring by drilling holes in RCC Work including necessary bending, hooking of dowel bars and grouting the holes complete as per detailed drawing and as directed.	275.00	Nos.	MR	250.00	2.50	252.50	69438.00
11	<b>GRILLS</b>							
11.1	Providing and fixing <b>12mm Bright Bars M.S. grills</b> and other fabrication work of required pattern to frames of windows etc. with M.S. flats at required spacings and frame around, square or round bars with round headed bolts and nuts or by screws (A) Plain Grill.	235.84	Kg	10025AA/102	108.00	1.08	109.08	25725.00
11.2	Providing and fixing in position <b>Collapsible steel shutters</b> with vertical channels 20 x 10 x 2 mm braced with flat iron diagonals 20 x 5 mm size with top and bottom rails of T_rin 40x 40 x 6 mm with 38mm dia, steel pulleys complete with bolts, nuts, locking arrangements, stoppers handles including applying a priming coat of red lead paint.	648.73	Kg	11003A/115	60.11	0.60	60.71	39384.00
11.3	Providing and fixing <b>Rolling shutters</b> of approved make made of 80 mm wide M.S. laths inter-locked together through their entire length and jointed together at the ends by end locks mounted on specially designed pipe shaft with bracket lates, guide channels and arrangements for inside and outside locking with push-pull operation including the cost of hood cover and spring etc. complete.(A) Shutters having width below 3.5 M.	16.35	Sqm	11005A/116	3519.21	35.19	3554.40	58100.00
11.4	Providing and fixing 27.5 cm. long wire spring grade No.2 of approved make for rolling shutters.	3.00	Nos	11007/116	630.91	6.31	637.22	1912.00
11.5	Providing and fixing Hood cover for rolling shutters (A) Shutters having width below 3.5 meters	7.04	Rmt	11008A/116	120.03	1.20	121.23	853.00
12	<b>PLUMBING</b>							
12.1	Providing and fixing Wall hung W.C of (CERA- CARAT) approved quality, including connecting the W.C with waste pipe, trap etc. complete as directed and approved by engineer incharge.	4.00	nos.	MR	5400.00	54.00	5454.00	21816.00
12.2	Providing and fixing metro pole of approved quality, including connecting Fixing , labour etc. complete as directed and approved by engineer incharge.(JAGUAR- 1093N)	4.00	nos.	MR	4390.00	43.90	4433.90	17736.00
12.3	Providing and fixing 2-WAY BIB COCK of approved quality, including connecting Fixing , labour etc. complete as directed and approved by engineer incharge. (JAGUAR)	4.00	nos.	MR	2300.00	23.00	2323.00	9292.00
12.4	Providing and fixing hand spray in toilets of approved quality, including connecting Fixing , labour etc. complete as directed and approved by engineer incharge.(JAGUAR- H.F.565)	4.00	nos.	MR	1360.00	13.60	1373.60	5494.00
12.5	Providing and fixing 15mm dia. bibcock of approved quality, including connecting Fixing , labour etc. complete as directed and approved by engineer incharge. (JAGUAR)	4.00	nos.	MR	2080.00	20.80	2100.80	8403.00
12.6	Providing and fixing washbasin with single hole for pillar tap with C.I. or M.S. brackets painted white including sutting holes and making good the same but excluding fittings.(A) (18"x14") (CERA-CADIS)	0.00	nos.	MR	2200.00	22.00	2222.00	0.00
12.7	Providing and fixing 15mm dia. Pillar cock of approved quality, including connecting Fixing , labour etc. complete as directed and approved by engineer incharge. (JAGUAR)	6.00	nos.	MR	2170.00	21.70	2191.70	13150.00
12.8	Providing and fixing 15mm dia. Angle cock of approved quality, including connecting Fixing , labour etc. complete as directed and approved by engineer incharge.(JAGUAR)	4.00	nos.	MR	1310.00	13.10	1323.10	5292.00
12.9	Providing and fixing C.P. brass waste pipe for washbasin or sink. (B) 40mm dia.	4.00	nos.	MR	640.00	6.40	646.40	2586.00
12.10	Providing and fixing washbasin with single hole for pillar tap with C.I. or M.S. brackets painted white including sutting holes and making good the same but excluding fittings (20"x16") (CERA-COUNSEL)	4.00	nos.	MR	2288.00	22.88	2310.88	9244.00
12.11	Providing and fixing SS Sink Glossy ASIS 304 Grade x 1mm thick with over all size 610 x 460 mm & bowl size 560 x 410 x 200 with single hole for pillar tap Fixing in sandwich platform including cutting holes and making goods the same including. necessary fixtures, connections and waste pipes.	2.00	Nos	MR	5650.00	56.50	5706.50	11413.00

12.12	Providing and fixing PVC SWR Nahni trap IS 14735 for drain - 100 mm diameter with jali of the following nominal diameter of self cleansing design with C.I. sread down or hinged grating including the cost of cutting and making good the walls.	6.00	Nos	23068	580.47	5.80	586.27	3518.00
12.13	Constructing <b>Brick masonry chamber</b> for underground C.I. Inspection chamber and bends with bricks having crushing strength not less than 35Kg/Cm2 in C.M. 1:5 C.I. cover with frame (Light duty) 455mm x 610mm intenal dimensions total weight of cover with frame to be not less than 38Kg. (Wt. of cover 23 Kg.) and Wt. of frame 15Kg. ) (R.C.C. top slabe with 1:2:4 mix (1-cement :2- coarse sand :4-graded stone aggregate 20mm size) foundation concrete 1:5:10 inside plaster 15mm thick with cement mortar 1:3 finished smooth with a floating coat of neat cement on walls and bed concrete etc. complete.(i) Inside dimensions 455mmx 610mm and 450mm deep for single pipe line.	2.00	Nos	24016AA/174	2903.89	29.04	2932.93	5866.00
12.14	Providing and fixing Urinal of approved (JAGUAR)quality including connection with trap and with integral longitudinal flush pipe.(A) Squating plate pattern white earthenware 550mm x 300mm.	2.00	Nos	23034/166	1612.41	16.12	1628.53	3257.00
12.15	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [B] 20 mm.	33.00	Rmt	23056/167	206.73	2.07	208.80	6890.00
12.16	Providing laying and jointing in true line and level 40mm dia. U.P.V.C. Pipe ( SCH- 40) for cold water including fittings as approved by Engineer In Charge. Pipe shall be fixed on the wall with the help of clamp at every two metre C/C or shall be concealed as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.	11.00	Rmt	23064/167	146.65	1.47	148.12	1629.00
12.17	Providing laying and jointing in true line and level 50mm dia. U.P.V.C. Pipe ( SCH- 40) for cold water including fittings as approved by Engineer In Charge. Pipe shall be fixed on the wall with the help of clamp at every two metre C/C or shall be concealed as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.	33.00	Rmt	23065/167	193.73	1.94	195.67	6457.00
12.18	Providing, laying and jointing in true line and level 40 diameter U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 40 mm diameter at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	27.50	Rmt	MR	388.00	3.88	391.88	10777.00
12.19	Providing, laying and jointing in true line and level 75 diameter U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 75 mm diameter at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	8.80	Rmt	MR	589.00	5.89	594.89	5235.00
12.20	Providing, laying and jointing in true line and level 110 diameter U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 110 mm diameter x 149 mm length x 145 mm heigh at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	11.00	Rmt	23067/169	868.22	8.68	876.90	9646.00

12.21	Providing erecting and fixing three layer virgin plastic white color ISI water tank of required capacity each with all necessary fittings and connection etc. complete on terrace	1000.00	litre	MR	8.50	0.09	8.59	8590.00
<b>13</b>	<b>FURNITURE WORK</b>							
13.1	Providing & fixing <b>Soft board</b> with 12 mm ply as per detailed drawing with all materials and labours etc. complete	3.00	Nos	RA	3700.00	37.00	3737.00	11211.00
13.2	Making and fixing <b>Tables</b> in plywood (sizes as required / as per drawings) finished with 1 mm Delta-SF-795 laminate and Corian as per given detailed drawings.i) Table (For Basement & FF Staff - Size : 1.36 x 0.69)	7.00	Nos	RA	21900.00	219.00	22119.00	154833.00
13.3	Making and fixing <b>Tables</b> in plywood (sizes as required / as per drawings) finished with 1 mm Delta-SF-795 laminate and Corian as per given detailed drawings.i) Table (For GF Staff - Size : 1.61 x 0.76)	4.00	Nos	RA	27600.00	276.00	27876.00	111504.00
13.4	Making and fixing <b>Tables</b> in plywood (sizes as required / as per drawings) finished with 1 mm Delta-SF-795 laminate and Corian as per given detailed drawings.i) Table (For GF Officer - Size : 1.67 x 0.69)	2.00	Nos	RA	27600.00	276.00	27876.00	55752.00
13.5	Making and fixing <b>Tables</b> in plywood (sizes as required / as per drawings) finished with 1 mm Delta-SF-795 laminate and Corian as per given detailed drawings.i) Table (For FF Officer - Size : 2.13 x 0.61)	2.00	Nos	RA	32700.00	327.00	33027.00	66054.00
13.6	Making and fixing <b>Tables</b> in plywood (sizes as required / as per drawings) finished with 1 mm Delta-SF-795 laminate and Corian as per given detailed drawings.i) Table (For GF & FF Manager - Size : 2.00 x 0.68)	2.00	Nos	RA	32200.00	322.00	32522.00	65044.00
13.7	Making and fixing <b>Tables</b> in plywood (sizes as required / as per drawings) finished with 1 mm Delta-SF-795 laminate and Corian as per given detailed drawings.i) Table (For For Cashier - Size : 1.61 x 0.76)	2.00	Nos	RA	35500.00	355.00	35855.00	71710.00
13.8	Making and fixing <b>Trolley / Movable Drawer</b> Installed with necessary hardware & Both Side 1mm Delta-SF-795 Laminate finish as per specification and drawing. Rates are inclusive with all materials, labours, Side Channel, handles, fastenings etc. complete	19.00	Nos	RA	17700.00	177.00	17877.00	339663.00
13.9	Making and fixing <b>Full Height Cupboards</b> with plywood (sizes as required / as per drawings) finished with 1mm Delta-SF-795 laminate outside and inside, Stainless Steel latch, lock, handles etc. complete. All biddings are finished with natural polishing. The rates are included with Selves, Drawers as per detailed Drawing. (The Measurement of cupboard is taken as height & width only for quantity.)	102.50	Sqm	RA	14200.00	142.00	14342.00	1470026.00
13.10	Making and fixing <b>3" Thick plywood Partition</b> finished with 1mm Delta-SF 795 laminate on both the sides as per detailed drawing.(Note: In partition, Glass will be measured seperately)	103.46	Sqm	RA	6400.00	64.00	6464.00	668733.00
13.11	Providing and Fixing <b>12 mm Fixed toughened Glass</b> Partition with all necessary hardware materials etc and as per directed by Engineer-incharge.	29.80	Sqm	RA	4500.00	45.00	4545.00	135436.00
13.12	Making and fixing <b>12 mm toughened Glass Doors</b> : Installed with floor spring, "H" handle and necessary hardware as per specification and drawing. For various Door widths specify as per Detailed Drawing. Rates are inclusive of all material and labours etc. completed Glass Door	14.32	Sqm	RA	9400.00	94.00	9494.00	135973.00
13.13	Making and fixing <b>Committee Table</b> in plywood (sizes as required / as per drawings) finished with 1 mm Delta-SF-795 laminate and Corian work as per given detailed drawing.i) Table (Committee Table - Size : 3.35m X 1.36m)	1.00	Nos	RA	84800.00	848.00	85648.00	85648.00
13.14	Making and fixing <b>35mm Thick Flush Doors</b> : Installed with necessary hardware & Both Side 1mm Delta-SF-795 Laminate finish as per specification and drawing. Rates are inclusive with all materials, labours, hinges, handles, fastenings etc. complete(Flush Door)	32.00	Sqm	RA	6400.00	64.00	6464.00	206848.00
13.15	Supplying and installing in position <b>25mm wide Horizontal Wooden venetian blinds/Curtain</b> with Thread System of Navin or equivalent (as approved by ID / Bank) in the window openings. (Measurement of blinds is taken as height & width)	31.10	Sqm	RA	5500.00	55.00	5555.00	172744.00
13.16	Providing <b>2 Seater Sofa set</b> Including All Material and Labour work of Described in drawing by Engineer In charge	2.00	Nos.	MR	15000.00	150.00	15150.00	30300.00
13.17	Providing <b>4 Seater Sofa set</b> Including All Material and Labour work of Described in drawing by Engineer In charge	2.00	Nos.	MR	30000.00	300.00	30300.00	60600.00

13.18	Making <b>Drop Box &amp; Suggestion Box</b> having sides is making with 18mm thick plywood and white laminate finish, back side of box is make with white laminate finish on 12mm thick plywood, top of the Box is make by 75mm curve in flexible plywood with delta White laminate SF Finish, 18mm X 18mm thick Border around this box with Orange Delta laminate finish, Delta Laminate sheet for Front Elevation of Box, Openable Door with 25mm X 50mm consealed handle and (Europa/Godrej) Lock and Key, (All Detailing as per selection base on RNSB color theme Suggestion & Drop Box	3.00	Each	MR	4800	48.00	4848.00	14544.00
13.19	Making <b>Pamphlet Board</b> (1200mm X 1000mm) with sandwich plywood (18mm X 18mm = 36mm thick & 36mm wide) Plywood with orange Delta laminate sheet SF Finish with 18 Gauge MS Perforated sheet with white powder coating including 25mm X 50mm Adustable hook for rest of Pamphlet, Including fitting, fastening & Adhesive materials(All Detailing as per selection base on RNSB color theme) Pamphlet Board	1.00	Each	MR	3910	39.10	3949.10	3949.00
13.20	Making Writing Desk with 18mm plywood with white delta laminate finish and 12mm plywood for partition with white delta laminate finish & 12mm Toughen Galss top of Writing Desk Including all necessary fitting, fastening & Adhesive materials. (All Detailing as per selection base on RNSB color theme and as per drawing).	2.00	Each	MR	3390	33.90	3423.90	6848.00
13.21	Making <b>Advertisement Board</b> (1200mm X 600mm) with 25mm X 36mm plywood Belt with Delta laminate sheet and 18 Gauge MS Perforated sheet with powder coating including SS Pin/Magnet for advertisement (All Detailing as per selection base on RNSB color theme) Advertisement Board 1	1.00	Each	MR	2520	25.20	2545.20	2545.00
13.22	Making <b>Notice Board</b> (900mm X 900mm) with 36mm X 36mm plywood with Delta laminate sheet SF Finish, 18 MM Plywood with Orange Delta laminate sheet for side Border and back side white laminate SF finish (0.8mm) and 18 Gauge MS Perforated sheet with powder coating including MS Pin/Magnet for advertisement Including fitting, fastening & Adhesive materials (All Detailing as per selection base on RNSB color theme) Notice Board	1.00	Each	MR	2651.4	26.51	2677.91	2678.00
13.23	Making <b>Advertisement Board</b> (750mm X 750mm) with 25mm X 36mm plywood Belt with Delta laminate sheet and 18 Gauge MS Perforated sheet with powder coating including SS Pin/Magnet for advertisement Including fitting, fastening & Adhesive materials (All Detailing as per selection base on RNSB color theme)	1.00	Each	MR	1850	18.50	1868.50	1869.00
13.24	Providing <b>Perforated Sheet Dustbin</b> having size 10" X 14" Inches Including all taxes and Transportation.	3.00	Each	MR	780	7.80	787.80	2363.00
13.25	Providing and fixing <b>12mm thick panelling</b> with one side 1mm thick laminate Delta SF-795 including required frame, materials, labor, transportation etc complete as per instructed by site incharge.	20.00	Sq.mt	MR	2700	27.00	2727.00	54540.00
14	<b>ELECTRICAL ITEMS (LABOUR WORK RATE)</b>							
14.1	Lighting Point	248.00	nos.	MR	250.00	2.50	252.50	62620.00
14.2	6 A , 16 A plug point	50.00	nos.	MR	330.00	3.30	333.30	16665.00
14.3	A/C Point	20.00	nos.	MR	500.00	5.00	505.00	10100.00
14.4	Circuit Point (MCB)	15.00	nos.	MR	750.00	7.50	757.50	11363.00
14.5	Terminal Lugs (8 nos set)	2.00	nos.	MR	830.00	8.30	838.30	1677.00
14.6	Panel Light Fitting (2'x2' and 15W DOWNLIGHT)	86.00	nos.	MR	100.00	1.00	101.00	8686.00
14.7	Booch Fitting	1.00	nos.	MR	100.00	1.00	101.00	101.00
14.8	Roof Top Solar Piping + Wiring	1.00	nos.	MR	2500.00	25.00	2525.00	2525.00
14.9	Water Solar Wiring	1.00	nos.	MR	1500.00	15.00	1515.00	1515.00
14.10	Motor Auto Level Guard Wiring	1.00	nos.	MR	1500.00	15.00	1515.00	1515.00
14.11	Main Board Fitting (main MCCB panel company)	3.00	nos.	MR	2000.00	20.00	2020.00	6060.00
14.12	Wall Light Fitting	1.00	nos.	MR	80.00	0.80	80.80	81.00
14.13	Profile Light Fitting	1.00	METER	MR	100.00	1.00	101.00	101.00
14.14	Anchor Bolt Fitting	26.00	nos.	MR	150.00	1.50	151.50	3939.00

